



March 27, 2014

Sound Level Test (Decibel)

Model P900

Test Equipment: Simpson Sound Level Meter, Model 886-2

Range: 40 - 140 dB

Weighting - 'A' (OSHA), Response - Slow

The unit under test (P900) is equipped with grills on the intake (front) and discharge (top) openings and was sitting on a table.

The unit was equipped with the standard filters and a variable speed control which comes standard on the unit.

Location: 24 inches from the front of the unit.

<u>Model</u>	<u>Speed</u>	<u>Sound Level (dB)</u>
P900	Maximum	57
	Minimum	47

DB P900.docx